



Assemble anchor bolts to template as shown above.  
Install bottom of template flush with top of finished grade.

Note: template must be installed level in both directions.

Note: drawing not too scale

Typical Anchor Bolt Installation			
TEMP: 92957			
STAMP	<b>STRUCTURA</b>		
	19922 W. 162nd Street Olathe, KS 66062		phone 913.390.8787 projects@structura.com
Duo XL Poles			
SHEET NUMBER	REVISED	DATE	DRAWING
1 of 1	#	4/13/2016	Duo XL - Anchor Bolt.idw